SCHEDULE - B

Name of the Work: Providing Sanitary Connection to the public toilet @ Bulleward Park in ward-18

Tender Notification: EE/H/TEND/01/12-13 date: 11/04/2012
Item No: 11

Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
1	Scarifying bituminous course 50mm to 75mm thick along with premix carpet/ surface dressing by manual means without disturbing the base and stacking of the debris materials within a lead of 100mtrs including cost of all labour charges etc., complete as per specifications and direction of the Engineer-in-Charge.	9.90	Sqm	44.00	Rupees Forty Four Only
2	Removing B.S. Slab drain and stacking, Refixing stone slabs of drains and pointing in C.M. (1:3) etc., complete as per specifications and direction of the Engineer-in-Charge.	13.60	Sqm	112.00	Rupees One Hundred Twelve Only
3	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50m and removing the debris to a distance upto 200m etc., complete as per specifications and direction of the Engineer-in-Charge.	1.04	Cum	137.00	Rupees One Hundred Thirty Seven Only
4	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m. in and above in width, in hard soil not exceeding 1.5 m. in depth including dressing in bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50m. after breaking of clods etc., complete as per specifications and direction of the Engineer-in-Charge	43.20	Cum	227.00	Rupees Two Hundred Twenty Seven Only
5	Constructing brick masonry inspection chamber 600x600mm and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I. cover with frame (light duty) 455 x 610mm internal dimensions, total weight of cover with frame to be not less than 38kg. (weight of cover 23kg. and weight of frame 15kg) RCC top slab with cement concrete 1:2:4 mix 20mm and down size granite metal, foundation concrete 1:5:10 with 40mm and down size granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing etc., complete as per specifications and direction of the Engineer-in-Charge	5.00	Nos	7250.00	Rupees Seven Thousand Two Hundred Fifty Only

Contractor

Executive Engineer (H)
Bruhat Bangalore Mahanagara Palike

Sl No	Description of Item	Quantity	Unit	Rate (Rs)	
				In figures	In words
6	KSRRB M200-14.1.Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 meters complete as per specifications. ii)Dismantling Brick/ Tile work. –do- Dismantling brick / Tile work B. in Cement mortar etc., complete as per specifications and direction of the Engineer-in-Charge.	0.90	Cum	200.00	Rupees Two Hundred Only
7	KSRB 12-1.1 . Providing and laying in position to required level or slope 150mm internal diameter salt glazed stone ware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per specifications. Providing and laying in position to required level or slope 150mm etc., complete as per specifications and direction of the Engineer-in-Charge.	50.00	Mtr	355.00	Rupees Three Hundred Fifty Five Only
8	Providing and Constructing granite /trap/ baslat size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc., complete as per specifications and direction of the Engineer-in-Charge.	1.89	Cum	3392.00	Rupees Three Thousand Three Hundred Ninety Two Only
9	Providing and Constructing granite /trap/ baslat size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15cms high, bond stones at two m. apart in each course including cost of materials, labour, curing with available stone etc., complete as per specifications and direction of the Engineer-in-Charge.	0.62	Cum	2465.00	Rupees Two Thousand Four Hundred Sixty Five Only
10	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc., complete as per specifications and direction of the Engineer-in-Charge.	5.20	Sqm	78.00	Rupees Seventy Eight Only

Contractor

Executive Engineer (H)
Bruhat Bangalore Mahanagara Palike

Sl No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
11	KSRB 4-1.6 Providing and laying in position plain cement concrete of mix M15 with cement @ 240 Kgs, with 20mm and down size graded granite metal coarse aggregtes @ 0.878 cum and line aggregates @ 0.459 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc., complete as per specifications and direction of the Engineer-in-Charge	3.57	Cum	4566.00	Rupees Four Thousand Five Hundred Sixty Six Only
12	Providing & fixing Unicorn tiles for footpath etc., complete as per specifications and direction of the Engineer-in-Charge.	7.20	Sqm	1260.00	Rupees One Thousand Two
13	Refixing of pipes etc , complete as per specifications and direction of the Engineer-in-Charge	43.20	Mtr	100.00	Rupees One Hundred Only

Contractor

Executive Engineer (H)
Bruhat Bangalore Mahanagara Palike